

ADVERTISEMENT FOR BIDS

Notice is hereby given that sealed bids will be received by the Township Committee of the Township of New Hanover, Burlington County, New Jersey, for the Hockamick Road Phase III (the "Project") until **11:00 AM prevailing time on April 5, 2023**, at which time the bids will be opened and publicly read aloud in the office of Municipal Building at 2 Hockamick Road, Cookstown, NJ 08511. Bids received after the designated time shall be deemed unresponsive and shall not be opened.

The project generally includes the milling and repaving of +/- 2,100 linear feet of Hockamick Road. In addition, improvements to driveway aprons, storm drainage inlets, striping and signage are also included in the project.

Drawings, specifications, and contract documents for the proposed Project, prepared by Environmental Resolutions, Inc., Consulting Engineers, have been filed in the Office of the township Engineer at 815 East Gate Drive – Suite 103, Mount Laurel, New Jersey 08054, and may be inspected by prospective bidders during normal business hours.

Bidders may obtain copies of the drawings, specifications and contract documents from the Office of the Township Engineer upon payment of Fifty Dollars and Zero Cents (\$50.00). Checks should be made payable to Environmental Resolutions Inc. The payment for such documents is non-refundable. If the bidder requires the documents to be mailed to them, there is an additional Fifteen Dollars and Zero Cents (\$15.00) fee for postage.

Bids must be made on the standard Bid form contained within the drawings, specifications, and contract documents, in the manner designated therein and required by the specifications. Further, bids must be enclosed in a sealed envelope bearing the name and address of the bidder and the Project title on the outside, and addressed to: Township Clerk, Township of New Hanover, 2 Hockamick Road, New Jersey 08511.

Each bid must be accompanied by (i) all documents listed on the Bid Document Submission Checklist, as applicable, and (ii) a bid guarantee in an amount not less than Ten Percent (10%) of the total bid price as established in the Bid, not to exceed Twenty Thousand Dollars and Zero Cents (\$20,000.00). The bid guarantee must be in the form of a bid bond, certified check, or cashier's check, must be drawn to the order of New Hanover Township and must be delivered simultaneous with the sealed bid.

Bidders are required to comply with the requirements of N.J.S.A. 10:5-31 et seq., N.J.A.C.17:27, and all other applicable laws referenced within the drawings, specifications and contract documents.

This project is being partially funded by an NJDOT grant.

The Township of New Hanover reserves the right to (i) reject all bids pursuant to N.J.S.A. 40A:11-13.2 and (ii) to waive minor informalities and/or non-material exceptions in any bid should it be in the interest of the Township of New Hanover to do so. Further, the Township of New Hanover shall reject any bid that contains material nonconformities or conditions, or which is materially nonresponsive. In the event the Township of New Hanover does not reject all bids as permitted under N.J.S.A. 40A:11-13.2, in accordance with N.J.S.A. 40A:11-4, and other applicable laws, the Project will be awarded to the lowest responsible bidder.

By order of the New Hanover Township Committee, Burlington County, New Jersey.

**HOCKAMICK ROAD PHASE III
 FY 2022 NJDOT MUNICIPAL AID
 TOWNSHIP OF NEW HANOVER
 CONSTRUCTION QUANTITIES**



**ENVIRONMENTAL
 RESOLUTIONS, INC.**
Engineers • Planners • Scientists • Surveyors

Environmental Resolutions
 815 East Gate Drive, Suite 103
 Mt. Laurel, NJ 08054
 P: (856) 235-7170

| NO | DESCRIPTION | QUANTITY | UNIT | UNIT PR. | AMOUNT |
|---------------------------|---|----------|------|----------|--------|
| ROAD IMPROVEMENTS: | | | | | |
| 1 | Base Repair, If and Where Directed | 500.0 | SY | | |
| 2 | 2" Milling | 5,949.0 | SY | | |
| 3 | 6" Milling | 2,084.0 | SY | | |
| 4 | HMA 19M64 Base Course, 4" Thick | 64.0 | TON | | |
| 5 | HMA 9.5M64 Surface Course, 2" Thick | 748.0 | TON | | |
| 6 | Remove and Replace Asphalt Driveway Apron | 279.0 | SY | | |
| 7 | Reconstruct Inlet, Type B | 3.0 | UN | | |
| 8 | Reconstruct Inlet, Type E | 1.0 | UN | | |
| 9 | Reconstruct Yard Drain | 1.0 | UN | | |
| 10 | Remove and Replace Inlet Head and Grate | 3.0 | UN | | |
| 11 | Turf Repair | 2,000.0 | LF | | |
| 12 | Remove and Replace Beam Guide Rail | 100.0 | LF | | |
| 13 | Remove and Replace Tangent Terminal | 100.0 | LF | | |
| 14 | Nonvegetative HMA Surface Course | 110.0 | SY | | |
| 15 | Remove and Replace Traffic Control Sign | 3.0 | UN | | |
| 16 | Long-Life Epoxy Striping, 4" Width | 6,080.0 | LF | | |
| 17 | Asphalt Price Adjustment | 400.0 | DOL | | |
| 18 | Fuel Price Adjustment | 200.0 | DOL | | |
| | | | | | |