

ADVERTISEMENT FOR BIDS

Notice is hereby given that sealed bids will be received by Delanco Township, Burlington County, New Jersey, for the Delanco 2023 Roadway Improvements, 3rd Street & Fenimore Lane (the "Project") until 11:00 AM prevailing time on September 28, 2023, at which time the bids will be opened and publicly read aloud in the Delanco Municipal Building at 770 Coopertown Road, Delanco, New Jersey 08075. Bids received after the designated time shall be deemed unresponsive and shall not be opened.

The Project generally includes: Milling and paving of approximately 6,000 SY of roadway, the removal and replacement of concrete curb and concrete flatwork, construction of ADA compliant ramps, installing thermoplastic striping, replacement of storm sewer Eco Heads and Bicycle Safe Grates, and other miscellaneous site work.

Drawings, specifications, and contract documents for the proposed Project, prepared by Environmental Resolutions, Inc., Consulting Engineers, have been filed in the Office of the Township Engineer at 815 East Gate Drive – Suite 103, Mount Laurel, New Jersey 08054, and may be inspected by prospective bidders during normal business hours.

Bidders may obtain copies of the drawings, specifications and contract documents from the Office of the Township Engineer upon payment of Fifty Dollars and Zero Cents (\$50.00). Checks should be made payable to Environmental Resolutions Inc. The payment for such documents is non-refundable. If the bidder requires the documents to be mailed to them, there is an additional Fifteen Dollars and Zero Cents (\$15.00) fee for postage.

Bids must be made on the standard Bid Form contained within the drawings, specifications, and contract documents, in the manner designated therein and required by the specifications. Further, bids must be enclosed in a sealed envelope bearing the name and address of the bidder and the Project title on the outside, and addressed to: Municipal Clerk, 770 Coopertown Road, Delanco, New Jersey 08075.

Each bid must be accompanied by (i) all documents listed on the Bid Document Submission Checklist, as applicable, and (ii) a bid guarantee in an amount not less than Ten Percent (10%) of the total bid price as established in the Bid, not to exceed Twenty Thousand Dollars and Zero Cents (\$20,000.00). The bid guarantee must be in the form of a bid bond, certified check, or cashier's check, must be drawn to the order of Delanco Township and must be delivered simultaneous with the sealed bid.

Bidders are required to comply with the requirements of N.J.S.A. 10:5-31 et seq., N.J.A.C.17:27, and all other applicable laws referenced within the drawings, specifications and contract documents.

This project is being partially funded by an NJDOT grant.

Delanco Township reserves the right to (i) reject all bids pursuant to N.J.S.A. 40A:11-13.2 and (ii) to waive minor informalities and/or non-material exceptions in any bid should it be in the interest of the Township to do so. Further, Delanco Township shall reject any bid that contains material nonconformities or conditions or which is materially nonresponsive. In the event the Township does not reject all bids as permitted under N.J.S.A. 40A:11-13.2, in accordance with N.J.S.A. 40A:11-4, and other applicable laws, the Project will be awarded to the lowest responsible bidder.

By order of the Committee of Delanco Township, Burlington County, New Jersey.

BASE BID – 3RD STREET FROM WALNUT STREET TO WILLOW STREET

Item	Description	Quantity	Unit Price	Amount
1.	Milling, 5" Thick	0 SY.	\$ <u>0.00</u>	\$ <u>0.00</u>
2.	Milling, 0"-2" Thick	3,250 SY.	\$ _____	\$ _____
3.	HMA 19M64 Base Course, 3" Thick	0 TONS.	\$ <u>0.00</u>	\$ <u>0.00</u>
4.	HMA 9.5M64 Surface Course, 2" Thick	400 TONS.	\$ _____	\$ _____
5.	Dense Graded Aggregate, 6" Thick	50 SY.	\$ _____	\$ _____
6.	Remove & Replace Concrete Curb 6"x8"x18"	225 LF.	\$ _____	\$ _____
6A.	Install Concrete Header Curb (If & Where Directed)	40 LF.	\$ _____	\$ _____
7.	Remove & Replace Concrete Apron, 6" Thick	10 SY.	\$ _____	\$ _____
8.	Remove & Replace Concrete Sidewalk, 4" Thick	180 SY.	\$ _____	\$ _____
9.	Install Detectable Warning Surface	18 SY.	\$ _____	\$ _____
10.	Install Steel Tree Plate	12 LF.	\$ _____	\$ _____
11.	Remove Tree, 12"-18"	1 UN.	\$ _____	\$ _____
12.	Remove & Replace Traffic Control Sign	1 UN.	\$ _____	\$ _____
13.	Remove & Replace Traffic Control Post	3 UN.	\$ _____	\$ _____
14.	Reset Inlet Casting	0 UN.	\$ <u>0.00</u>	\$ <u>0.00</u>
15.	Eco Head Replacement	0 UN.	\$ <u>0.00</u>	\$ <u>0.00</u>
16.	Bicycle Safe Grate Replacement	0 UN.	\$ <u>0.00</u>	\$ <u>0.00</u>
17.	Install Thermoplastic Stop Bar	11 SY.	\$ _____	\$ _____
18.	Install Thermoplastic Crosswalk Striping	86 SY.	\$ _____	\$ _____
19.	Re-Paint Curb Yellow	0 LF.	\$ <u>0.00</u>	\$ <u>0.00</u>
20.	Asphalt Price Adjustment	200 DOLL.	\$ <u>1.00</u>	\$ <u>200.00</u>
21.	Fuel Price Adjustment	200 DOLL.	\$ <u>1.00</u>	\$ <u>200.00</u>

BASE BID – FENIMORE LANE FROM BURLINGTON AVENUE TO END

Item	Description	Quantity	Unit Price	Amount
1.	Milling, 5” Thick	950 SY.	\$ _____	\$ _____
2.	Milling, 0”-2” Thick	2,750 SY.	\$ _____	\$ _____
3.	HMA 19M64 Base Course, 3” Thick	180 TONS.	\$ _____	\$ _____
4.	HMA 9.5M64 Surface Course, 2” Thick	460 TONS.	\$ _____	\$ _____
5.	Dense Graded Aggregate, 6” Thick	50 SY.	\$ _____	\$ _____
6.	Remove & Replace Concrete Curb 6”x8”x18”	130 LF.	\$ _____	\$ _____
6A.	Install Concrete Header Curb (If & Where Directed)	0 LF.	\$ <u>0.00</u>	\$ <u>0.00</u>
7.	Remove & Replace Concrete Apron, 6” Thick	23 SY.	\$ _____	\$ _____
8.	Remove & Replace Concrete Sidewalk, 4” Thick	70 SY.	\$ _____	\$ _____
9.	Install Detectable Warning Surface	5 SY.	\$ _____	\$ _____
10.	Install Steel Tree Plate	0 LF.	\$ <u>0.00</u>	\$ <u>0.00</u>
11.	Remove Tree, 12”-18”	0 UN.	\$ <u>0.00</u>	\$ <u>0.00</u>
12.	Remove & Replace Traffic Control Sign	0 UN.	\$ <u>0.00</u>	\$ <u>0.00</u>
13.	Remove & Replace Traffic Control Post	0 UN.	\$ <u>0.00</u>	\$ <u>0.00</u>
14.	Reset Inlet Casting	2 UN.	\$ _____	\$ _____
15.	Eco Head Replacement	4 UN.	\$ _____	\$ _____
16.	Bicycle Safe Grate Replacement	5 UN.	\$ _____	\$ _____
17.	Install Thermoplastic Stop Bar	2.5 SY.	\$ _____	\$ _____
18.	Install Thermoplastic Crosswalk Striping	30 SY.	\$ _____	\$ _____
19.	Re-Paint Curb Yellow	15 LF.	\$ _____	\$ _____
20.	Asphalt Price Adjustment	0 DOLL.	\$ <u>0.00</u>	\$ <u>0.00</u>
21.	Fuel Price Adjustment	0 DOLL.	\$ <u>0.00</u>	\$ <u>0.00</u>