

ADVERTISEMENT FOR BIDS

Notice is hereby given that sealed bids will be received by the Borough of Palmyra, Burlington County, New Jersey, for 2026 NJDOT Road Program (the "Project", Job #44539 00) **until 11:30 AM prevailing time on Tuesday, September 15, 2026**, at which time the bids will be opened and publicly read aloud at Borough Hall at 20 W. Broad Street, Palmyra, New Jersey 08065. Bids received after the designated time shall be deemed unresponsive and shall not be opened.

The Project generally includes roadway and miscellaneous related improvements to Memorial Avenue, Jefferson Street, Legion Avenue, Spring Garden Street, Lincoln Avenue, and Wallace Street in the Borough of Palmyra, Burlington County, New Jersey complete in every detail as shown or specified, for the prices bid in the Proposal.

Drawings, specifications, and contract documents for the proposed Project, prepared by Environmental Resolutions, Inc., Consulting Engineers, have been filed in the Office of the Borough Engineer at 815 East Gate Drive – Suite 103, Mount Laurel, New Jersey 08054, and may be inspected by prospective bidders during normal business hours.

Bidders may obtain copies of the drawings, specifications and contract documents from the Office of the Borough Engineer upon payment of Seventy-Five Dollars and Zero Cents (\$75.00). Checks should be made payable to Environmental Resolutions Inc. The payment for such documents is non-refundable. If the bidder requires the documents to be mailed to them, there is an additional Twenty Dollars and Zero Cents (\$20.00) fee for postage.

Bids must be made on the standard Bid form contained within the drawings, specifications, and contract documents, in the manner designated therein and required by the specifications. Further, bids must be enclosed in a sealed envelope bearing the name and address of the bidder and the Project title on the outside, and addressed to: Borough Clerk, 20 W. Broad Street, Palmyra, New Jersey 08065.

Each bid must be accompanied by (i) all documents listed on the Bid Document Submission Checklist, as applicable, and (ii) a bid guarantee in an amount not less than Ten Percent (10%) of the total bid price as established in the Bid, not to exceed Twenty Thousand Dollars and Zero Cents (\$20,000.00). The bid guarantee must be in the form of a bid bond, certified check, or cashier's check, must be drawn to the order of Borough of Palmyra and must be delivered simultaneous with the sealed bid.

Bidders are required to comply with the requirements of N.J.S.A. 10:5-31 et seq., N.J.A.C.17:27, and all other applicable laws referenced within the drawings, specifications and contract documents.

This project is being partially funded by an NJDOT grant.

The Borough of Palmyra reserves the right to (i) reject all bids pursuant to N.J.S.A. 40A:11-13.2 and (ii) to waive minor informalities and/or non-material exceptions in any bid should it be in the interest of the Borough of Palmyra to do so. Further, the Borough of Palmyra shall reject any bid that contains material nonconformities or conditions, or which is materially nonresponsive. In the event the Borough of Palmyra does not reject all bids as permitted under N.J.S.A. 40A:11-13.2, in accordance with N.J.S.A. 40A:11-4, and other applicable laws, the Project will be awarded to the lowest responsible bidder.

By order of the Council of the Borough of Palmyra, Burlington County, New Jersey.

Project Quantities as of September 15, 2026

Item	Description	Quantity	
1.	HMA Milling, 4"	7,900.0	SY
2.	Hot Mix Asphalt 19 M 64 Base Course, 2.5" Thick	1,176.0	TON
3.	Hot Mix Asphalt 19 M 64 Base Course, 2" Thick (If & Where Directed)	30.0	TON
4.	Hot Mix Asphalt 9.5 M 64 Surface Course, 1.5" Thick	720.0	TON
5.	Hot Mix Asphalt Pavement Repair (If & Where Directed)	500.0	SY
6.	Dense Graded Aggregate, 6" Thick	240.0	SY
7.	Hot Mix Asphalt Driveway, 2" Thick	50.0	SY
8.	Parking Lot Restoration	70.0	SY
9.	Remove Concrete	240.0	SY
10.	Concrete Swale, 8" Thick	50.0	SY
11.	Concrete Driveway, 6" Thick	250.0	SY
12.	Concrete Sidewalk, 4" Thick	260.0	SY
13.	Concrete Vertical Curb, 6"x8"x18"	3,950.0	LF
14.	Monolithic Concrete Curb and Gutter	1,670.0	LF
15.	Steel Treeplate	170.0	LF
16.	Detectable Warning Surface	72.0	SF
17.	Remove Inlet	2.0	UN
18.	Remove Pipe	6.0	LF
19.	Construct Storm Manhole	1.0	UN
20.	Inlet, Type A	1.0	UN
21.	Inlet, Type B	5.0	UN
22.	Reconstructed Manhole, Using Existing Casting	1.0	UN
23.	Reconstructed Inlet, Type A, Using Existing Casting	1.0	UN
24.	Reconstructed Inlet, Type B, Using Existing Casting	9.0	UN
25.	Reconstructed Inlet, Type E, Using Existing Casting	2.0	UN
26.	Parge Inlet	4.0	UN
27.	Curb Piece	6.0	UN
28.	Bicycle Safe Grate	3.0	UN
29.	Grout Existing Pipe	2.5	CY
30.	Construct 16" DIP	20.0	LF
31.	Construct 12" DIP	110.0	LF
32.	Construct 18" PCPP	75.0	LF
33.	Construct 15" PCPP	445.0	LF
34.	Install 6" Stormwater Valve	2.0	UN

Project Quantities as of September 15, 2026

Item	Description	Quantity	
35.	Regulatory and Warning Sign	15.0	UN
36.	Traffic Stripes, 4"	130.0	LF
37.	Traffic Markings Lines, 6"	130.0	LF
38.	Traffic Markings Lines, 24"	240.0	LF
39.	Curb Painting	620.0	LF
40.	Tree Removal, Over 12" to 18" Diameter	1.0	UN
41.	Topsoil and Seed, 4" Thick (If & Where Directed)	8.0	SY
42.	Cleanout Monument Box (If & Where Directed)	2.0	UN
43.	Repair Sewer Lateral Cleanout Riser (If & Where Directed)	2.0	UN
44.	Repair Sewer Lateral Cleanout Riser and Tee (If & Where Directed)	2.0	UN
45.	Fuel Price Adjustment	600.0	DOL
46.	Asphalt Price Adjustment	1,200.0	DOL