ADVERTISEMENT FOR BIDS

Notice is hereby given that sealed bids will be received by the Township of Medford, Burlington County, New Jersey, for **"FY2026 NJDOT Municipal Aid Grant, Christopher's Mill Road, Taunton Road To Ohio Trail, FY2025 Road Improvement Program"** ERI # 25954 25, until **1:00 PM** prevailing time on **December 9, 2026**, at which time the bids will be opened and publicly read aloud in the office of the Township Clerk at 49 Union Street, Medford, NJ, 08055. Bids received after the designated time shall be deemed unresponsive and shall not be opened.

The Project Base Bid generally includes approximately 23,725 SY of variable depth milling, and approximately 2,880 tons bituminous surface course paving of roadways, selective base repair, resetting of castings and valve boxes, selective bituminous driveway apron replacement, traffic striping, traffic signage replacement, and related appurtenances on Christopher's Mill Road, Middlegate Drive, North Wendover Avenue, and Heath Road. Alternate Bid No. 1 on Headwater Drive Sta. 36+00 to Sta. 60+10 Stokes Road includes milling 2" thick for 9,500 SY and overlaying 2" thick of 1,150 tons of HMA, HMA pavement repair (If & Where Directed), selective bituminous driveway apron replacement, traffic sign replacement, and traffic striping, and related appurtenances. Alternate Bid No. 2 on Stafford Circle Road and Eden Circle Road includes milling 2" thick for 3,460 SY and overlaying 2" thick of 415 tons of HMA, HMA pavement repair (If & Where Directed), selective bituminous driveway apron replacement, and related appurtenances. Alternate Bid No. 3 on Headwater Drive Stokes Road Sta. 00+25 to Sta. 36+00 includes milling 2" thick for 15,525 SY and overlaying 2" thick of 1,880 tons of HMA, HMA pavement repair (If & Where Directed), and selective bituminous driveway apron replacement, 28 LF of 15" RCP, and related appurtenances. Alternate Bid No. 4 on South Lakeside Drive East includes 192 LF of 24" RCP, one 5' x 7' drainage structure, tree removal, and related appurtenances. Alternate Bid No. 5 on Filbert Street & Bank Street includes 2 'A' inlets, 45 LF of 12" HDPE pipe, base repair and 5 tons of bituminous surface course paving. Alternate Bid No. 6 on Headwater Drive Sta. 36+00 to Sta. 60+10 Stokes Road is 265 LF of guide rail installations.

Drawings, specifications, and contract documents for the proposed Project, prepared by Environmental Resolutions, Inc., Consulting Engineers, have been filed in the Office of the Township Engineer at 815 East Gate Drive – Suite 103, Mount Laurel, New Jersey 08054, and may be inspected by prospective bidders during normal business hours.

Bidders may obtain copies of the drawings, specifications and contract documents from the Office of the Township Engineer upon payment of One Hundred Dollars and Zero Cents ($100.00). Checks should be made payable to Environmental Resolutions Inc. The payment for such documents is non-refundable. If the bidder requires the documents to be mailed to them, there is an additional Twenty Dollars and Zero Cents ($20.00) fee for postage.

Bids must be made on the standard proposal form contained within the drawings, specifications, and contract documents, in the manner designated therein and required by the specifications. Further, bids must be enclosed in a sealed envelope bearing the name and address of the bidder and the Project title on the outside, and addressed to: Township Clerk, Township of Medford, 49 Union Street, Medford, NJ, 08055.

Each bid must be accompanied by (i) all documents listed on the Bid Document Submission Checklist, as applicable, and (ii) a bid guarantee in an amount not less than Ten Percent (10%) of the total bid price as established in the proposal, not to exceed Twenty Thousand Dollars and Zero Cents ($20,000.00). The bid guarantee must be in the form of a bid bond, certified check, or cashier's check, must be drawn to the order of Township of Medford and must be delivered simultaneous with the sealed bid.

Bidders are required to comply with the requirements of N.J.S.A. 10:5-31 et seq., N.J.A.C.17:27, and all other applicable laws referenced within the drawings, specifications and contract documents.

The Christopher's Mill Road portion of the project is partially funded by NJDOT Municipal Aid.

Township of Medford reserves the right to (i) reject all bids pursuant to N.J.S.A. 40A:11-13.2 and (ii) to waive minor informalities and/or non-material exceptions in any bid should it be in the interest of the Township of Medford to do so. Further, Township of Medford shall reject any bid that contains material nonconformities or conditions, or which is materially nonresponsive. In the event Township of Medford does not reject all bids as permitted under N.J.S.A. 40A:11-13.2, in accordance with N.J.S.A. 40A:11-4, and other applicable laws, the Project will be awarded to the lowest responsible bidder.
By order of the Medford Township Council, Burlington County, New Jersey.

FORM OF PROPOSAL

For the construction of the FY2026 NJDOT Municipal Aid Grant, Christopher's Mill Road, Taunton Road To Ohio Trail, FY2025 Road Improvement Program and related work in the Township of Medford, Burlington County, New Jersey:

The undersigned, as bidder, declares that:

(1) (s)he has carefully examined the annexed Advertisement for Proposals, Specifications, and forms for Contract and Bond, and the accompanying drawings therein mentioned;

(2) (s)he has received, examined and taken into full account the provisions of Addenda Number _____, dated _____.
(if none, so state)

(3) (s)he has familiarized himself with all Federal, State and local laws, ordinances, rules and regulations affecting the proposed Project;

(4) (s)he has visited the sites of the work and made such independent investigations as he deems necessary; and

(5) (s)he has examined fully into the conditions, costs and expenses involved in the performance of the proposed work;

and (s)he hereby proposes and agrees that if this proposal is accepted (s)he will enter into contract with the Township of Medford, in the County of Burlington, to provide the necessary equipment, machinery, tools, power, labor, services, hauling, superintendence and all materials and things required for, and will do and perform all work of installation, construction and completion of the entire Project described in said Specifications and/or illustrated on the drawings, all in entire accordance with the requirements of the said Specifications, for the following prices, to wit:

BASE BID

Christopher's Mill Road is partially funded by a NJDOT Municipal Aid Grant for the year 2026.

Item	Description	Quantity	Unit Price	Amount
1.	HMA Milling 2" Or Less	10,150 S.Y.	$_____	$_____
2.	Base Repair (if and where directed)	1,750 S.Y.	$_____	$_____
3.	HMA 9.5M64 Surface Course, 2" Thick	1,250 Tons	$_____	$_____
4.	HMA Driveway, 3" Thick	325 S.Y.	$_____	$_____
5.	Concrete Driveway, 6" Thick	10 S.Y.	$_____	$_____
6.	Curb Piece	1 Unit	$_____	$_____
7.	Bicycle Safe Grate	4 Units	$_____	$_____

Item	Description	Quantity	Unit Price	Amount
8.	Warning Sign	2 Units	$_____	$_____
9.	Regulatory Sign	1 Unit	$_____	$_____
10.	Traffic Striping, 4”	13,750 L.F.	$_____	$_____
11.	Traffic Striping, 12” Thermoplastic	200 L.F.	$_____	$_____
12.	Stop Bar, 24” Thermoplastic	15 L.F.	$_____	$_____
Asphalt & Fuel Adjustment Prices				
13.	Asphalt Price Adjustment	1 Dollar	$1,500.00	$1,500.00
14.	Fuel Price Adjustment	1 Dollar	$800.00	$800.00

BASE BID All Other Roads.
The following roads are also included in the Base Bid: Middlegate Drive, North Wendover Avenue, and Heath Road.

Item	Description	Quantity	Unit Price	Amount
15.	HMA Milling 1.5” Or Less	1,325 S.Y.	$_____	$_____
16.	HMA Milling 2” Or Less	12,250 S.Y.	$_____	$_____
17.	Base Repair (if and where directed)	2,100 S.Y.	$_____	$_____
18.	Dense Graded Aggregate, 6" Thick	115 S.Y	$_____	$_____
19.	HMA 9.5M64 Surface Course, 2" Thick	1,630 Tons	$_____	$_____
20.	HMA Driveway, 3” Thick	150 S.Y.	$_____	$_____
21.	Curb Piece	2 Units	$_____	$_____
22.	Warning Sign	8 Units	$_____	$_____
23.	Regulatory Sign	3 Units	$_____	$_____
24.	Street Sign	1 Unit	$_____	$_____
25.	Traffic Stripes, 4”	520 L.F.	$_____	$_____
26.	Stop Bar, 24” Thermoplastic	20 L.F.	$_____	$_____
27.	Test Pit	2 Units	$_____	$_____
28.	1” Copper Water Service (if & where directed)	2 Units	$_____	$_____

Item	Description	Quantity	Unit Price	Amount
29.	Borrow Excavation (If & Where Directed)	3 Tons	$_____	$_____
30.	Undercut & Subgrade Materials (If & Where Directed)	3 C.Y.	$_____	$_____

Asphalt & Fuel Adjustment Prices

31.	Asphalt Price Adjustment	1 Dollar	$1,900.00	$1,900.00
32.	Fuel Price Adjustment	1 Dollar	$1,000.00	$1,000.00

TOTAL AMOUNT BASE BID

$_____

_____ Dollars_____ Cents.
(The total amount is to be shown in both words and figures. In case of discrepancy the amount shown in words will govern.)

ALTERNATE BID NO. 1

Headwater Drive – Stokes Road Sta. 00+25 To Sta. 36+00

Item	Description	Quantity	Unit Price	Amount
A1.	HMA Milling 2” Or Less	15,525 S.Y.	$_____	$_____
A2.	Base Repair (if and where directed)	3,150 S.Y.	$_____	$_____
A3.	HMA 9.5M64 Surface Course, 2" Thick	1,880 Tons	$_____	$_____
A4.	HMA Driveway, 3” Thick	380 S.Y.	$_____	$_____
A5.	Bituminous Curb	425 L.F.	$_____	$_____
A6.	Curb Piece	5 Units	$_____	$_____
A7.	Bicycle Safe Grate	6 Units	$_____	$_____
A8.	Parge Inlet	5 Units	$_____	$_____
A9.	Warning Sign	1 Unit	$_____	$_____
A10.	Angular Stone Riprap Slope Protection (D50=6”) With Filter Fabric	16 C.Y.	$_____	$_____
A11.	Stop Bar, 24” Thermoplastic	24 L.F.	$_____	$_____
A12.	15” RCP Class IV	28 L.F.	$_____	$_____

Item	Description	Quantity	Unit Price	Amount
Asphalt & Fuel Adjustment Prices				
A13.	Asphalt Price Adjustment	1 Dollar	$2,400.00	$2,400.00
A14.	Fuel Price Adjustment	1 Dollar	$1,200.00	$1,200.00

TOTAL AMOUNT ALTERNATE BID NO. 1

$_____

_____ Dollars_____ Cents.
(The total amount is to be shown in both words and figures. In case of discrepancy the amount shown in words will govern.)

TOTAL AMOUNT BASE BID & ALTERNATE BID NO. 1 $_____

_____ Dollars_____ Cents.
(The total amount is to be shown in both words and figures. In case of discrepancy the amount shown in words will govern.)

ALTERNATE BID NO. 2

Stafford Circle Road & Eden Circle Road

Item	Description	Quantity	Unit Price	Amount
B1.	HMA Milling 2” Or Less	3,460 S.Y.	$_____	$_____
B2.	Base Repair (if and where directed)	700 S.Y.	$_____	$_____
B3.	HMA 9.5M64 Surface Course, 2" Thick	415 Tons	$_____	$_____
B4.	HMA Driveway, 3” Thick	150 S.Y.	$_____	$_____
B5.	Bicycle Safe Grate	2 Units	$_____	$_____

TOTAL AMOUNT ALTERNATE BID NO. 2

$_____

_____ Dollars_____ Cents.
(The total amount is to be shown in both words and figures. In case of discrepancy the amount shown in words will govern.)

TOTAL AMOUNT BASE BID, ALTERNATE BID NO. 1 & ALTERNATE BID NO. 2 $_____

_____ Dollars_____ Cents.
(The total amount is to be shown in both words and figures. In case of discrepancy the amount shown in words will govern.)

ALTERNATE BID NO. 3

Headwater Drive – Sta. 36+00 To Sta. 60+10 Stokes Road

Item	Description	Quantity	Unit Price	Amount
C1.	HMA Milling 2” Or Less	9,500 S.Y.	$_____	$_____
C2.	Base Repair (if and where directed)	1,900 S.Y.	$_____	$_____
C3.	HMA 9.5M64 Surface Course, 2" Thick	1,150 Tons	$_____	$_____
C4.	Dense Graded Aggregate 6” Thick	15 S.Y.	$_____	$_____
C5.	HMA Driveway, 3” Thick	220 S.Y.	$_____	$_____
C6.	Curb Piece	2 Units	$_____	$_____
C7.	Bicycle Safe Grate	2 Units	$_____	$_____
C8.	Reconstruct Inlet	1 Unit	$_____	$_____
C9.	Warning Sign	1 Unit	$_____	$_____
C10.	Regulatory Sign	2 Units	$_____	$_____
C11.	Stop Bar, 24” Thermoplastic	15 L.F.	$_____	$_____
C12.	Bituminous Curb	55 L.F.	$_____	$_____
Asphalt & Fuel Adjustment Prices				
C13.	Asphalt Price Adjustment	1 Dollar	$1,500.00	$1,500.00
C14.	Fuel Price Adjustment	1 Dollar	$700.00	$700.00

TOTAL AMOUNT ALTERNATE BID NO. 3

$_____

_____ Dollars_____ Cents.
(The total amount is to be shown in both words and figures. In case of discrepancy the amount shown in words will govern.)

TOTAL AMOUNT BASE BID, ALTERNATE BID NO. 1, ALTERNATE BID NO. 2 & ALTERNATE BID NO. 3 $_____

_____ Dollars_____ Cents.
(The total amount is to be shown in both words and figures. In case of discrepancy the amount shown in words will govern.)

ALTERNATE BID NO. 4

South Lakeside Drive East Drainage Improvements

Item	Description	Quantity		Unit Price	Amount
D1.	24" RCP	192	L.F.	$_____	$_____
D2.	5' X 7' Drainage Structure	1	Unit	$_____	$_____
D3.	Tree Removal 8"-12" Dia. (if & where directed)	2	Units	$_____	$_____
D4.	Tree Removal >12"-16" Dia. (if & where directed)	3	Units	$_____	$_____
D5.	Tree Removal >16"-20" Dia. (if & where directed)	1	Unit	$_____	$_____
D6.	Tree Removal >20"-24" Dia. (if & where directed)	1	Unit	$_____	$_____
D7.	Tree Removal >24"-27" Dia. (if & where directed)	1	Unit	$_____	$_____
D8.	Borrow Excavation (if & where directed)	750	Tons	$_____	$_____
D9.	Undercut & Subgrade Materials (if & where directed)	150	C.Y.	$_____	$_____
D10.	6" Topsoil, Seed , Fertilizer & Mulch	272	SY	$_____	$_____

TOTAL AMOUNT ALTERNATE BID NO. 4

$_____

_____ Dollars_____ Cents.

(The total amount is to be shown in both words and figures. In case of discrepancy the amount shown in words will govern.)

TOTAL AMOUNT BASE BID, ALTERNATE BID NO. 1, ALTERNATE BID NO. 2, ALTERNATE BID NO. 3 & ALTERNATE BID NO. 4 $_____

_____ Dollars_____ Cents.

(The total amount is to be shown in both words and figures. In case of discrepancy the amount shown in words will govern.)

ALTERNATE BID NO. 5

Filbert Street & Bank Street Drainage Improvements

Item	Description	Quantity	Unit Price	Amount
E1.	HMA 9.5M64 Surface Course, 2" Thick	5 Tons	$_____	$_____
E2.	Base Repair	20 S.Y.	$_____	$_____
E3.	'A' Inlet With ADA Safe Grate	1 Unit	$_____	$_____
E4.	'A' Inlet With Bicycle Safe Grate	1 Unit	$_____	$_____
E5.	12" HDPE Pipe	45 LF	$_____	$_____

TOTAL AMOUNT ALTERNATE BID NO. 5

$_____

_____ Dollars_____ Cents.
(The total amount is to be shown in both words and figures. In case of discrepancy the amount shown in words will govern.)

TOTAL AMOUNT BASE BID, ALTERNATE BID NO. 1, ALTERNATE BID NO. 2, ALTERNATE BID NO. 3, ALTERNATE BID NO. 4 & ALTERNATE BID NO. 5 $_____

_____ Dollars_____ Cents.
(The total amount is to be shown in both words and figures. In case of discrepancy the amount shown in words will govern.)

ALTERNATE BID NO. 6

Headwater Drive – Stokes Road Sta. 00+25 To Sta. 36+00

Item	Description	Quantity	Unit Price	Amount
F1.	Tangent Guide Rail Terminal	2 Units	$_____	$_____
F2.	Beam Guide Rail	265 L.F.	$_____	$_____
F3.	Guide Rail Terminal	2 Units	$_____	$_____
F4.	Beam Guide Rail As-Built	1 L.S.	$_____	$_____

TOTAL AMOUNT ALTERNATE BID NO. 6

$_____

_____ Dollars_____ Cents.
(The total amount is to be shown in both words and figures. In case of discrepancy the amount shown in words will govern.)

TOTAL AMOUNT BASE BID, ALTERNATE BID NO. 1, ALTERNATE BID NO. 2, ALTERNATE BID NO. 3, ALTERNATE BID NO. 4, ALTERNATE BID NO. 5 & ALTERNATE BID NO. 6 $_____

_____ Dollars_____ Cents.

(The total amount is to be shown in both words and figures. In case of discrepancy the amount shown in words will govern.)

CONTRACTOR_____
partnership

The undersigned is a corporation under the laws of the State of _____
individual
having principal offices at

ADDRESS_____

CITY_____

STATE_____ZIP_____

TELEPHONE_____FAX_____

Attest _____ Signed _____
(Corporation)
Title _____ Title _____

Date _____